Technical Specifications
Inclusions

PERTH CONVENTION AND EXHIBITION CENTRE

The below technical items are included within your venue hire.

Stage Lighting
- 10x ECL Prolights CT+ LED Profiles 15-30 degree (stage wash)
- Lighting Bars & Truss
- Lighting Rail 3 (scissor lift access – hire cost for lift POA)
- Lighting Bridge 2 (via Catwalk)
- Lighting Bridge 1 (via Catwalk)
- 8 x 1 Ton I Beam
- 2 x Follow spot landings at top-rear corners of Theatre (holds permanently installed follow spots - see exclusions)
- Lighting Rail 3 capacity 100kg/m plus 500kg each hanging point
- Bridge lighting rail load capacity 100kg/m
- Structural hanging point capacity 500kg each
- 2 x Mid rigging points 950kg

Above Stage
- 45m x 450mm Box Truss 1 (Holds permanently installed cvc lights and installed LED screen (see exclusions)
- 20m x 500mm Box Truss 2 (Clear of any installed equipment)
- 20m x 500mm Box Truss 3 (Holds permanently installed items - see exclusions)
- 12m x 290mm Box Truss 4 (Holds permanently installed items - see exclusions)

Staging
- 1x Cyclorama (white scrim) 20m x 10m;
- 1x Black Curtain (parted from middle and closes in front of cyc)

Please note: there is no front of house curtain.

In-House Audio System
- 2x Lectrum Aero Series Lecterns
- 2x Shure MX412 lectern microphones
- Hearing induction loop

Other
- Loading dock ramp installation and removal

PERTH CONVENTION AND EXHIBITION CENTRE

21 Mounts Bay Road
Perth WA 6000

P: +61 8 9475 3318
P: +61 458 477 636

W: pcec.com.au

Technical Specifications
Exclusions

The following is not included within the venue hire fee for the **Riverside Theatre**, these items are available on request through AVPartners.

Vision
- 20m x 5m 2.6mm pitch LED screen - 400 x 500mm x 500mm panels (option for up to 120 x 500mm x 500mm additional panels)
- 1 x Novastar H5 LED Controller (additional LED controllers available on request)
- 1 x Magnimage V16 Vision Switcher
- 1 x Magnimage H9 Control Surface
- 6 x Intel NUC PC, Win 11,
- 1 x Mac Studio

Audio
- d&b audiotechnik xSL Line Array PA system, consisting of:

Hangs
- 12 x d&b audiotechnik XSL 8 Loudspeaker (on 40D amplifier, array processed)
- 8 x d&b audiotechnik XSL 12 Loudspeaker (on 40D amplifier, array processed)
- 4 x d&b audiotechnik SL-SUB Subwoofer, flown (on D80 amplifier)

Centre Fill
- 3 x d&b audiotechnik AL60 Loudspeaker (on 40D amplifier)

Front Fill
- 8 x d&b audiotechnik E8 Loudspeaker (on 5D amplifier)

Foldback
- 8x d&b M4 Stage Monitors (on D80 amplifier)

Consoles
- 1 x Yamaha CL5 72 channel console
- 1 x Yamaha RIO 3224
- 1 x Yamaha RIO 1608

FOH Drive Rack
- Lake LMX48
- APB DynaSonics MixSwitch Console
- V9 Smaart RT Rig with M83R Earthworks Reference Mic
- Intel NUC PC with R1 control
- UPS

Lighting
Lighting plot is available from AVPartners on request
- 6 x Prolight EcIProfile CT+, 15-30 degrees (note, 10 already included with venue hire)
- 20 x Vshow S711 LED Framing Light
- 8 x Prolights Astrawash Pix19 LED
- 14 x Ayrton Mistral LED Moving Profile
- 2 x Unique 2.1 Haze Machines - Usage is subject to meeting the firewatch requirements of PCEC
- 2 x RJLED 600w Followspots
- 2x ArtNet/sACN node
- Lighting console is available upon request (subject to availability)

Other:
- Hollyland Solidcom M1 Wireless talkback system (up to 16 packs)
- 1x set of 5m 400amp power lock tails (no distribution)

All installed items can be removed or relocated upon request at an additional cost.
Please contact AVPartners for more information.

PERTH CONVENTION AND
EXHIBITION CENTRE

21 Mounts Bay Road
Perth WA 6000

P: +61 8 9475 3318
P: +61 458 477 636

W: pcec.com.au